

1



As soon as your Altegra Gazebo is assembled and at the correct height we recommend to have one person hold the centre of the frame whilst the other person hammers the pegs through any of the 3 positions in the foot plates.

For windy conditions use 2 pegs per leg as desired.

If you are setting up on a hard surface please utilise our sandbag or steel leg weight options below.

2



Always use the guy ropes provided for additional tie down purposes.

Feed the rope through the canopy eyelets and around the inside of the upper frame leg. Once through the eyelets tie a secure knot on the outside of the canopy. This step can be done prior to raising the leg heights.

3



Peg the guy rope pieces firmly in the ground between a 15-45 degree angle from the top.

Optional Extras

